

Tender No. TPCODL/P&S/1000000189/21-22
"Electrification of UEHs by providing Service Connection under PMAY-G and BGJY schemes"

Replies to Pre-Bid Queries

S. No.	Clause no / Page No.	Description	Bidders query / Clarification	TPCODL Response / Modification
1	Page no 69 of 112 BOQ Sr. No 1	Single Phase Static Meter, Class 1.0, smart meter compatible with states existing metering system, 10-60A, 240 Volts with FRP based sheet moulding compound (SMC) 2.5 mm thick confirming to IS:13410 (1992)	List of makes not available PI provide the same	List of preferred manufacturer is mentioned in technical specifications. If bidder proposes any other OEM, bidder shall mandatory submit three samples for testing and factory evaluation will be done as per TPCODL vendor evaluation process.
2	Page no 69 of 112 BOQ Sr. No 2	Twin Core (unarmoured) PVC Insulated Cable of size 4.0 sq. mm with Aluminium Conductor as per REC Specification 26/1983 with average length of 27 meter per connection	Request to provide us specification, GTP, List of makes	Any reputed make with ISI Marked conforming to IS:648-1990 (amended upto date)
3	Page no 69 of 112 BOQ Sr. No 3	GI Pipe of 25 mm dia medium class confirming to IS:1161 with two nos. supporting clamps of size 40X3 MS Flat as per REC Construction Standard H-1	Qty Mentioned in nos. Request you to give us length of each pipe	Approx. 3 mtr. including bends
4	Page no 69 of 112 BOQ Sr. No 4	ISI mark, 240 V, 16A Double Pole Miniature Circuit Breaker	Request to provide us breaking capacity , specification, List of makes	Any reputed make with ISI Marked conforming to IEC-60898
5	Page no 69 of 112 BOQ Sr. No 5	1.5 sq. mm PVC Copper Multi Standard PVC Insulated Wire as per BIS Specification	Request to provide us specification List of makes	Any reputed make with ISI Marked conforming to IS:694-1990 (ammended upto date)
6	Page no 69 of 112 BOQ Sr. No 7,8	Piano Type 5A, 240 V ISI Mark Switch, 5A, 240 V ISI Mark Three Pin Socket	Request to provide us specification List of makes	Any reputed Make with ISI Marked conforming to IS:1293-2005 (for Socket) & IS:3854-1997 (for Switch)
7	Page no 69 of 112 BOQ Sr. No 11	LED Lamp of 9 Watts, 144-288 Volts operating voltage	Request to provide us specification List of makes	Any reputed make conforming to IS 16101-2012

Tender No. TPCODL/P&S/1000000189/21-22
"Electrification of UEHs by providing Service Connection under PMAY-G and BGJY schemes"

Replies to Pre-Bid Queries

S. No.	Clause no / Page No.	Description	Bidders query / Clarification	TPCODL Response / Modification
8	Page no 69 of 112 BOQ Sr. No 16	Installation Charges of Meter and Kit	PI clarify Installation Charges means whether we have to put erection rate of Meter only or associated item & we pre-assumed in item no 1 (supply of meter) only supply rate will be considered , installation charges will be covered in item no 16--PI confirm	Installation of all items including meter, cable and other accessories to be quoted against S. No. 16 only
9	Page no 110 of 112 Drawing	Service Connection Single Phase Drawing	Avilable drawing is unreadable --Kindly provide the same for better understading	Drawing given for referance . Can be rared as per site requirement.
10	General	List of makes	Approved list of make is not avilable PI provide the same	Any reputed brand with ISI mark / confirming to relevant IS.
11	Page no 14 of 112 (7.5 Payment Terms)	a. 90 % payment shall be released within 30 days of bill submission at designated desk. b. 10% payment shall be released after safety, quality parameter and material reconciliation verification by EIC or within 60 days from receipt of bill, if no issue is reported by EIC, whichever is earlier.	Request to you add 10% advance of project cost in paymet terms clause	As per tender
12	Page no 19 of 112 ANNEXURE IV SCHEDULE OF COMMERCIAL SPECIFICATIONS Sr. No 6	Liquidated damages clause acceptable	Tender document Liquidated damage not avilable .It is requested to make L.D. @0.5% per week of delay or part thereof limited to maximum of 5% of the cost of the undelivered portion of the materials/equipment and incomplete portion of works. Please confirm.	As per tender. Refer GCC Clause 15.0 for details

Tender No. TPCODL/P&S/1000000189/21-22
"Electrification of UEHs by providing Service Connection under PMAY-G and BGJY schemes"

Replies to Pre-Bid Queries

S. No.	Clause no / Page No.	Description	Bidders query / Clarification	TPCODL Response / Modification
13	Annexure-1 price bid format page no 69	Single Phase Static Meter, Class 1.0, smart meter compatible with states existing metering system, 10-60A, 240 Volts with FRP based sheet moulding compound (SMC) 2.5 mm thick confirming to IS:13410 (1992)	But in the specification it imentioned as Single Phase Class 1, 10-60 Amp, DLMS Compliant Whole Current Energy Meter with Meter box. Hence smart meter is required or DLMS compliant?	DLMS static meter is required.
14	-	-	Please specify approved make of Raw materials	Bidder to comply with tender specification.
15	page no 13	BA shall ensure completion of the electrification works including Supply of Meters and Service Connection kit within 60 days of the issue of Release Order or Manufacturing Clearance, whichever is later.	can you specify tentavive qty to be supplied and erected within 60 days?	Release Orders shall be issued as per requirement. Bidder to ensure the completion of the electrification works including Supply of Meters and Service Connection kit within 60 days of the issue of Release Order or Manufacturing Clearance, whichever is later.